# RBridge Channel Tunnel draft-ietf-trill-channel-tunnel-04

Donald E. Eastlake, 3<sup>rd</sup>


d3e3e3@gmail.com

## The RBridge Channel Facility

- TRILL switches need a way to sent control messages to each other including multi-hop and multi-destination control messages. For example, BFD messages [RFC7175] since the BFD standard only specifies the payload, not an envelope.
- Such control messages are addressed by nickname (or distribution tree if multi-destination), since a TRILL switch it not guaranteed to have an IP or MAC address (it could have all PPP ports).
- The RBridge Channel feature [RFC7178] provides this facility.
- A message type ("channel protocol") field is included in the RBridge Channel header.

## The RBridge Channel Facility (cont.)

This is what it looks like at a high level:




 It is also useful to be able to send control messages between TRILL switches and end stations. In this case, the messages are addressed by MAC address since end stations connect by Ethernet:

Ethernet	RBridge Channel	Type Specific	FCS
Header	Header	Payload	

#### So what does Channel Tunnel Add?

- 1. The [RFC7178] RBridge Channel facility provides no security. That may be OK if the control message being carriedhas its own security, such as BFD, but is bad in general.
- 2. A way to tunnel standard payload types such as RBridge Channel messages, Ethernet frames, etc.
- By combining 1 and 2 above, Channel Tunnel lets you tunnel an RBridge Channel Message with security. This is currently used in draft-ietf-trill-directory-assistmechanisms to security Pull Directory requests an responses.

#### **Channel Tunnel**



5

## Changes since January Meeting

- -02 > -03 > -04
- Security improvements
  - Add DTLS based security
  - Add IS-IS keying based encryption and authentication
- Remove the "Scope" feature
  - Too complex and no demonstrated need

### Question

- Currently specified channel tunnel payload types are:
  - 1. Null
  - 2. RBridge Channel message
  - 3. TRILL Data packet
  - 4. TRILL IS-IS packet
  - 5. Ethernet Frame
- Currently, for types 2, 3, and 4, there is no initial EtherType after the Channel Tunnel header.
- Proposal: Include EtherType and collapse payload types 2, 3, and 4 into one.

## Questions / Action

Questions?

#### • Actions:

- Resolve the question,
- Polish the draft a bit, post a revision, and

TRILL Channel Tunnel

Do a WG Last Call.